



- NOTES:**
1. RETAINING WALLS OVER 1.0m SHALL HAVE A 1.2m HIGH RINGLOCK AND STAR IRON PICKET FENCE INSTALLED ON TOP.
 2. TO BE READ IN CONJUNCTION WITH RETAINING WALL LONGSECTION, STANDARD RETAINING WALL DETAILS AND EARTHWORKS DRAWINGS.
 3. ADD EXTRA BLOCKS AS INDICATED ON ELECTRICAL DRAWING

- LEGEND**
- PROPOSED RETAINING WALLS
 - - - FUTURE RETAINING WALLS
 - EXISTING RETAINING WALLS
 - 23 — FINISHED GROUND LEVELS
 - RW 'A' RETAINING WALL REFERENCE
 - [23.25] LOT LEVEL

TWO COURSE WALL SETOUT INFORMATION

WALL No.	VERGE RL	FRONT OF WALL RL	BACK OF WALL RL	TOP OF WALL RL	LENGTH
8	28.94	28.95	29.32	29.37	25.50
9	29.67	29.69	30.06	30.11	25.50
10	29.25	29.32	29.69	29.74	25.50
22	29.80	30.11	30.48	30.53	25.50
23	29.58	29.74	30.11	30.16	25.50
29	31.52	31.57	31.94	31.99	22.20
30	31.16	31.20	31.57	31.62	22.20
33	32.37	32.31	32.68	32.73	25.51
34	32.60	32.68	33.05	33.10	25.51
35	30.48	30.46	30.83	30.88	25.50


REFER STANDARD WALL DETAILS FOR TYPICAL SECTION

WALLS 6, 10, 11 & 40 TO BE CONSTRUCTED UNDER SEPARATE APPROVAL



No.	DATE	BY	REVISION
1	30/01/18	JTH	WALL 10 DELETED FROM CONTRACT
2	29/01/18	JTH	WALLS 6, 11, 40 DELETED FROM CONTRACT, ISSUED FOR CONSTRUCTION
3	12/01/18	JTH	EXTENT OF WORK AT SOUTHERN BOUNDARY AMENDED, TREES REMOVED
4	14/12/17	JTH	TREE PICK-UP ADDED
5	21/09/17	SWW	LOT LEVELS AND RETAINING WALLS REVISED
6	7/06/17	JTH	WALLS ALONG ROAD 4 ADDED/EXTENDED, WALL 44 ADDED
7	12/03/18	SWW	ROAD NAMES ADDED

CLIENT: **TERRANOVIS PTY LTD**



SUITE 3, 123A COLIN ST, WEST PERTH, 6005 WESTERN AUSTRALIA
Ph: (08) 94.81 1900
Fax: (08) 94.81 1700

PROJECT: **LOTS 2 & 3 ANKETELL ROAD ANKETELL-STAGE 1A**
W.A.P.C. No. - 153400 & 153398

DRAWING: **EARTHWORKS RETAINING WALLS LAYOUT PLAN**
CAD DRAWING DO NOT MANUALLY ALTER

SCALE	DRAWN	CHECK	REV No.
1:250	JTH	SRA	2
DATE	DESIGNED	APPROVED	
24/03/17	SWW	SRA	
PROJECT NUMBER		DRAWING NUMBER	
ANKTER11 E03			